

THE CITY OF LEHI IS REQUESTING PROPOSALS TO BUILD ONE AQUATIC WATERSLIDE, SLIDE TOWER AND A RUNOUT PUMP PACKAGE WITH THE ABILITY TO ADD ANOTHER WATERSLIDE TO THE TOWER IN THE FUTURE.

ADDENDUM #1:

1-5-2012

The following information shall be included as part of the requirements and conditions of your proposal as if a part of the original RFP. Please acknowledge receipt of this addendum as part of your proposal.

1. Please provide engineering and installation of new footings for all support of the slide and stairs.
2. The slide contractor will provide UV water treatment for the slide(s) sized according to code and health department requirements.
3. Lehi City will be responsible for demolition, extension and installation of the perimeter fencing as required to meet the new pool enclosure configuration.
4. The slide contractor will provide a minimum 5,500 gal. underground water tank as a part of the at the pump package system.
5. Lehi City will be responsible for installation of all utilities on the site to within 5' of the exterior wall of the equipment building.
6. The slide contractor will provide a minimum 400,000 BTU heater to each slide provided including all equipment required for complete installation and operation.
7. Construction documents and installation of all pool equipment and other construction will require Health Department and Building Department approval.
8. Engineered and stamped construction documents from an engineer licenced in the State of Utah will be required for submittal to all required agencies.
9. Contractor shall be required to hold a General Contractors license in the State of Utah. Please provide your Utah license number as part of your proposal

END OF ADDENDUM #1