

Addendum 2 Pre-bid Meeting Clarifications

A2.1 Changes to Bathroom Plans

The following is a description of the changes to the plans that Lehi City has made.

- LED cans will be used instead of the specified fixtures.
- The tie in will be to the sewer system no the septic tank.
- Porcelain fixtures will be used instead of stainless steel.
- The toilets will not be auto flush.
- There will be no hand-dryers. Lehi City will install towel dispensers.
- The partitions should be made of plastic or a composite instead of metal.
- Floors will be polished and sealed concrete.
- The brick will be sealed.

A2.2 Liquidated Damages after Final Completion Date

Once the bid is awarded, the City and the Contractor will set a Final Completion Date as a part of the Contract Documents. If the Contractor's delay makes the damages applicable, the Contractor agrees that they will pay liquidated damages in the amount of \$100.00 per day for each day after the final completion date.