



NOTES:

1. METER SOCKET: 100 AMPS OR 200 AMPS.
2. METER SOCKET WITH TEST BLOCKS.
3. MAIN BREAKER: 100 AMP OR 200 AMP, 100K AIC.
4. UTILITY LANDING LUGS: 200 AMPS, 250 KCMIL.
5. 12-GAUGE CORROSION-RESISTANT ZINC-COATED STEEL CONSTRUCTION, HOOD AND COVERS 14-GAUGE.
6. RAINPROOF TYPE 3R ENCLOSURE.
7. COMPLIES WITH CALTRANS SPECIFICATION ES-2E.
8. MEETS EUSERC 308 REQUIREMENTS.
9. ALL FACTORY WIRING IS 600 VOLT RATED COPPER.

DRAWING: LES, JWG-03, L, REVISED/AFKIL-4/10



REQUIREMENTS & STANDARDS
PEDESTAL METER
100-400 AMP (1 OR 3 PHASE)
TYPICAL INSTALLATION

DWG: **3.2.4**

REV. 0.00

BY: GWK/BT

DATE:05/18/19