NOTES:

- 1. DEVELOPER/CONTRACTOR SHALL PROVIDE AND INSTALL ALL REQUIRED CONDUITS, AS SHOWN ON THE CIRCUIT ROUTING PLANS.
- 2. SECONDARY JUNCTION BOXES SHALL BE PROVIDED BY LEHI AND INSTALLED BY DEVELOPER/CONTRACTOR.
- 3. SEE CIRCUIT PLAN FOR EQUIPMENT LOCATIONS. EQUIPMENT SHALL BE CENTERED ON LOT LINES TO THE EXTENT POSSIBLE. OTHER LOCATIONS AS REQUIRED OR SHOWN ON THE CIRCUIT ROUTING PLAN.
- 4. DO NOT OBSTRUCT ACCESS TO POWER BOXES; MAINTAIN 3' CLEAR EXCEPT AS NOTED. PROVIDE 10' CLEARANCE ON CABINET ACCESS SIDES.
- 5. LEHI POWER SHALL PROVIDE, PULL & TERMINATE CONDUCTORS.
- 6. BASES SHALL BE PLACED ON FULL DEPTH COMPACT ENGINEERED FILL COMPACTED TO 95% MAX DENSITY. EXTEND COMPACTED BASE MATERIAL AS REQUIRED TO MAINTAIN STABLE SUPPORT. REFER TO 4.2.1
- 7. EQUIPMENT BASES SHALL BE SET LEVEL AND ALIGNED WITH THE WALK OR ADJACENT ENTITIES TO PROVIDE A NEAT APPEARANCE.
- 8. CONDUIT AND EQUIPMENT SHALL BE PLACED AFTER CURB, GUTTER AND WALK TO ASSURE CORRECT PLACEMENT VERTICALLY AND HORIZONTALLY WITHIN THE EASEMENT.
- 9. FOR DEVELOPMENT WITHOUT WALKS, PLACE EQUIPMENT 3' MINIMUM 5' MAXIMUM BEHIND CURB.



SECONDARY
JUNCTION BOX
(SECONDARY PEDESTAL)

(LOCATIONS IN THE P.U.E.)

DWG: **4.1.2**REV. 0.00
BY: GWK/BT
DATE: 3/10/17