

- 1. DEVELOPER/CONTRACTOR SHALL PROVIDE AND INSTALL ALL CONDUITS AND GROUND RODS
- 2. LEHI POWER SHALL PROVIDE EQUIPMENT BASES TO BE INSTALLED BY DEVELOPER/CONTRACTOR
- 3. BASES SHALL BE PLACED ON FULL DEPTH COMPACT ENGINEERED FILL COMPACTED TO 95% MAX DENSITY. EXTEND COMPACTED BASE MATERIAL AS REQUIRED TO MAINTAIN STABLE SUPPORT. REFER TO 4.2.1
- 4. SEE CIRCUIT PLAN FOR EQUIPMENT LOCATIONS.
- 5. DO NOT OBSTRUCT ACCESS TO POWER BOXES; MAINTAIN 3' MINIMUM CLEARANCE EXCEPT AS NOTED.
- PROVIDE 10' CLEARANCE ON CABINET ACCESS SIDES.
- 7. LEHI POWER SHALL PROVIDE AND SET CABINETS; PROVIDE, PULL & TERMINATE CONDUCTORS
- 8. EQUIPMENT BASE SHALL BE SET LEVEL AND ALIGNED WITH THE WALK OR ADJACENT ENTITIES
- 9. CONDUIT AND EQUIPMENT BASES SHALL BE PLACED AFTER CURB, GUTTER AND WALK TO ASSURE CORRECT PLACEMENT WITHIN THE EASEMENT.



NOTES:

**REQUIREMENTS & STANDARDS** 

GROUND SLEEVE/ SECTIONALIZER

(TYPICAL LOCATION IN THE P.U.E.)

DWG: **4.1.4** 

REV. 0.00

BY: GWK/BT

DATE: 03/28/17