



NOTES:

- 1 PROVIDE #4 BARS @ 12" O.C. BOTH WAYS IN 3,000 PSI CONCRETE ON COMPACTED BASE.
- 2 INSTALL 5/8 X 8' COPPER CLAD GROUND ROD WITHIN PRIMARY COMPARTMENT.
- 3 LEHI CITY POWER INSPECTION REQUIRED PRIOR TO CONCRETE PLACEMENT.
- 4 REQUIRED ACCESS CLEARANCE FOR BOTH SIDES AND REAR OF PAD 3 FT. MIN.
- 5 REQUIRED ACCESS CLEARANCE IN FRONT OF PAD 10 FT. MIN..



**REQUIREMENTS & STANDARDS
TRANSFORMER PAD
3 PHASE
UNDERGROUND SERVICE**

DWG: **4.1.8**

REV. 0.00

BY: EB/BT

DATE: 11/10/17