



NOTES:

- * 1. NO TERMINALS IN THESE 2 POSITIONS ON 13 TERMINAL SOCKET. 9 TERMINAL SOCKET RECOMMENDED, 15 SOCKET IS ACCEPTABLE (FORM 8S & 9S METERS).
- 2. APPROXIMATE DIMENSIONS: 4.5"(D) X 12"(W) X 20"(H).
- 3. METER SOCKET SHALL BE SEALABLE BY LEHI CITY POWER.
- 4. METER SOCKET SHALL HAVE TEST SWITCH COMPARTMENT TO MOUNT 9.5" TEST SWITCH. TEST SWITCH SUPPLIED AND INSTALLED BY LEHI CITY POWER.
- 5. LEHI CITY POWER SHALL WIRE METER SOCKET, CT'S AND TEST SWITCH.



REQUIREMENTS & STANDARDS
METER SOCKET 400 AMP AND UP
WIRING DIAGRAM
3 WIRE WYE/1 PHASE
120/208 277/480 VOLT
9 TERMINAL SOCKET

DWG: 6.2.2
REV. 0.00
BY: GWK/BT
DATE: 6/6/16